

## Clean Air Branch Standard Comments

### Construction/Demolition Involving Asbestos:

If the proposed project includes renovation/demolition activities which may involve asbestos, the applicant should contact the Asbestos Abatement Office in the Noise, Radiation and Indoor Air Quality Branch at 586-5800.

### Control of Fugitive Dust:

A significant potential for fugitive dust emissions exists during all phases of construction and operations. Proposed activities that occur in proximity to existing residences, businesses, public areas or thoroughfares, exacerbate potential dust problems. It is recommended that a dust control management plan be developed which identifies and addresses all activities that have a potential to generate fugitive dust. The plan, which does *not* require DOH approval, would help with recognizing and minimizing the dust problems from the proposed project.

Activities must comply with the provisions of Hawaii Administrative Rules, §11-60.1-33 on Fugitive Dust. In addition, for cases involving mixed land use, we strongly recommend that buffer zones be established, wherever possible, in order to alleviate potential nuisance problems.

The contractor should provide adequate measures to control the fugitive dust from the road areas and during the various phases of construction. Examples of measures that can be implemented to control dust include, but are not limited to, the following:

- a) Planning the different phases of construction, focusing on minimizing the amount of dust-generating materials and activities, centralizing on-site vehicular traffic routes, and locating potential dust-generating equipment in areas of the least impact;
- b) Providing an adequate water source at the site prior to start-up of construction activities;
- c) Landscaping and providing rapid covering of bare areas, including slopes, starting from the initial grading phase;
- d) Minimizing dust from shoulders and access roads;
- e) Providing adequate dust control measures during weekends, after hours, and prior to daily start-up of construction activities; and
- f) Controlling dust from debris being hauled away from the project site.

If you have any questions, please contact the Clean Air Branch at 586-4200.

(6/15/05)