

Appendix F to Chapter 12-133.2
Perimeter Columns: Non-Mandatory Guidelines for
Complying with Section 12-133.2-8(e) To Protect the Unprotected Side or Edge
of a Walking/Working Surface

In multi-story structures, when holes in the column web are used for perimeter safety cables, the column splice must be placed sufficiently high so as not to interfere with any attachments to the column necessary for the column splice. Column splices are recommended to be placed at every other or fourth levels as design allows. Column splices at third levels are detrimental to the erection process and should be avoided if possible.